



Project Management Office (PMO)
Sindh Barrages Improvement Project (SBIP)
IRRIGATION DEPARTMENT

Irrigation Colony near Adjacent City School PAF Chapter Baloch Colony, Karachi
Website: www.sbip.org.pk
Phone # 021-99330185

Date: 19-12-2022

REQUEST FOR QUOTATIONS

Reference No: - PK-AFOF SBIP - 296323 -GO-RFO

The Government of Sindh through Irrigation Department is implementing Sindh Barrages Improvement Project, Rehabilitation and Modernization of Sukkur Barrage AF (Project ID No. P 131324) with financial assistance of the World Bank under International Development Association (IDA) No. 62420-PK. Project Management Office, Sindh Barrages Improvement Project established within the Irrigation Department invites sealed quotations from the reputed GST registered Firms, Manufactures, Authorized Dealers and Distributors having previous experience to provide following type of Electric Generator 150KVA and Water Pump.

S.No	Item with Specification	Quantity No.	Rate Rs.	Amount Rs.
01.	<p><u>SUPPLY AND INSTALLATION OF ELECTRIC GENERATOR (3-PHASE), DIESEL ENGINE TYPE WITH LOW SOUND CANOPY.</u></p> <ul style="list-style-type: none">• Capacity: 150 KVA (3-Phase).• Brushless & AVR Type AMF Module.• Electric – Start, low noise, delta connection control panel, 3-Phase 4 pole.• 1200- 1500 RPM diesel Engine water & air cool type.• Voltage: 380 / 415, frequency 50 to 60 Hz.	01		
02.	<p><u>SUPPLY AND INSTALLATION OF PUMPS (MOBILE PUMP SET)</u></p> <ul style="list-style-type: none">• Mobile diesel engine trolley mounted water pump (agriculture grade).• Engine type: Diesel water cool, 25 Hp, 1200 RPM.• Impellor: Brass material, 18” dia.• Suction & Delivery 8 inch; total head 10ft.• Trolley Type: 4 Wheel, Toeing arrangement with 2400cc vehicle (double cabin).	01		

	<ul style="list-style-type: none"> Pipe: 8” dia flexible PVC 50ft (Suction), 200ft cotton canvas pipe (delivery). 			
		Total		
		GST		
		Grand Total		

The Subject items will be procured under Procurement Guide Lines of the World Bank.

Companies having previous experience supply of above items may quote their competitive prices on or before January 02, 2023.

Delivery time : Within 30 days after issuance of purchase order.

Mode of payment: Through crossed cheque after delivery/supply, installation and successful operation of items.

Place of Delivery: Office of the Director Hydrology & Research in Sindh, Hyderabad.

Address : Director Hydrology & Research in Sindh opposite Saima Plaza
Kali Mori, Hyderabad.

The delivery of Electric Generator and Pumps will be required within 30 days after issuance of purchase order. The quotations with complete details from the companies /authorized dealers may be addressed to the Project Director, PMO and submitted to the address given bellow by email or in person.

Project Director

Project Management Office

Sindh Barrages Improvement Project

Irrigation Department

Address: **Irrigation Colony near Adjacent City School PAF Chapter Baloch Colony,
Karachi.**